# MARYLAND HISTORICAL TRUST DETERMINATION OF ELIGIBILITY FORM

NR	Eligible:	yes	
		no	

Property Name: Johnson-Crump House Site	Inventory Number:	PG: 62-015
Address: 7606 Old Muirkirk Road	Historic district:	yes X no
City: Beltsville Zip Code: 20705	County: Prince	Georges
USGS Quadrangle(s): Beltsville		
Property Owner: Monita R. Crump-Sisco	Tax Account ID Number	10 1014026
Tax Map Parcel Number(s): 104 Tax M	Map Number: 13	
Project: US 1/ MD 201:Cherrywood Lane to North of Contee Road	Agency: SHA	
Agency Prepared By: EHT Traceries, Inc.		
Preparer's Name: Maria Dayton	Date Prepared:	1/10/2008
Documentation is presented in:		
Preparer's Eligibility Recommendation: Eligibility reco	mmended X Eligib	ility not recommended
Criteria: A B C D Considerations:	ABCD	_EFG
Complete if the property is a contributing or non-contributing	ng resource to a NR district/propert	y:
Name of the District/Property:		
Inventory Number: Eligible:	yes Listed:	yes
te visit by MHT Staff yes X no Name:		Date:
Description of Property and Justification: (Please attach map and photo	(0)	10
The single dwelling at 7606 Old Muirkirk Road was constructed circa 2 Maryland. It rests on the site of the Johnson-Crump House (PG: 62-15) Johnson-Crump House was a two-story, three-bay log house erected circurrent single dwelling occupied a sloping lot that features immature tre secondary resources associated with this property.	that had been destroyed by fire in Nova 1887. At the time of the Decemb	March 1981. The er 2007 survey, the
The two-story, five-bay single dwelling is set on a solid concrete foundarmain block has a symmetrical façade and is composed of elements come a projecting front gable and is covered in asphalt shingles. A one-and-northwest of the dwelling.	non of the Colonial Revival style. I	t has a hipped-roof with
The Johnson-Crump House was a result of the expansion of Beltsville a development and history of the area around U.S. Route 1, which travels Maryland, has been strongly influenced by its use as a major transportate.	north from Beltsville to Laurel in P	rince George's County,
MARYLAND HISTORICAL TRUST REVIEW		
Eligibility recommended Eligibility not recommend	led	
Criteria:ABCD Considerations:	ABCD	EFG
MHT Comments: NO LONGER EXTANT		
7. 70 01	planta	
Reviewer, Office of Preservation Services	8/28/8 Date	
N/A	Date	
Reviewer, National Register Program	Date	

Page 2


Washington and Baltimore Turnpike, which was established in 1812 to connect the commercial center of Baltimore with the new federal city of Washington. Shortly after the development of the turnpike, the railroad arrived in Prince George's County. By 1835, The Baltimore and Ohio Railroad established a station and freight depot on land purchased from Trueman Belt, and a small community developed around the rail stop, which was named after the former owner.(1) The Johnson-Crump House was built in the late nineteenth century as a part of this growing community.

Today, Route 1, also known as Baltimore Avenue (formerly Washington and Baltimore Turnpike), is bounded by commercial properties, many of which are automobile-oriented businesses dating from the early to mid-twentieth century. Nearby thoroughfares such as Old Baltimore Pike, Edmonston Road, and Maryland Avenue have a mix of commercial and industrial sites, with several residential properties. The former single dwelling at 7606 Old Muirkirk Road is an example of the development that took place in the Beltsville area in the last half of the nineteenth century. The edges of minor roads such as Old Muirkirk and Cochran Roads are predominately developed by freestanding single-family dwellings dating from the first part of the twentieth century. It was not until after World War II that intensive development came to the area along Route 1. With increased federal employment, rise in personal automobile ownership, and construction of Interstate 95, development along Route 1 and surrounding area continued through the 1960s.(1)

The single dwelling at 7606 Muirkirk Road was constructed circa 2001 on the site of the circa 1887 Johnson-Crump House, which was built during the late-nineteenth-century development of the Beltsville/Laurel area. However, this property is not individually associated with the events and trends that have made a significant contribution to the broad patterns of our history, thus disqualifying it for eligibility under Criterion A. The property is not associated with any person or group of persons of outstanding importance to the community, state, or nation. Therefore, the current single dwelling at 7606 Muirkirk Road is not eligible under Criterion B. Although this building is an example of early-twenty-first-century-domestic-architecture, it is a common building form in Prince George's County. This example is not significant as it does not represent the work of a master or possess high artistic value. Further, since the Johnson-Crump House was destroyed by fire, the integrity of its design, materials, workmanship, setting, feeling, association, and location as a late-nineteenth-century property has been lost. It is thus disqualified for eligibility under Criterion C. The building at 7606 Old Muirkirk Road was not evaluated under Criterion D. Therefore, it has been recommended that the former single dwelling at 7606 Old Muirkirk Road is not eligible for listing in the National Register of Historic Places under Criteria A, B, and C.

1) Susan G. Pearl, "History of Route 1 Corridor, 1740-1990," in Historic Contexts in Prince George's County: Short Papers on Settlement Patterns, Transportation and Cultural History (Upper Marlboro, MD: Maryland-National Capital Park and Planning Commission, 1991), 30.

MARYLA	ND HISTO	ORICAL	TRUST	REVI	EW							
Eligibility	recommen	ded		Eli	gibility not recommen	ded						
Criteria:	A	В	С	D	Considerations:	A	В	C	D	Е	F	G
MHT Com	ments:											
	Review	er, Offic	e of Pre	servatio	on Services			Date				
-	Revie	wer, Na	tional R	egister	Program	-		Date				




Johnson-Crump House Site (PG: 62-015), 7606 Old Muirkirk Road Beltsville, Prince George's County, MD


Beltsville, Prince George's County, MD Tax Parcel Map 13, Parcel 104 Prepared by EHT Traceries, Inc., 2008

N

## **RESOURCE SKETCH MAP**




ID#: P6:62-015	Name: Johnson - Crump House Site
10 11 11	Address: 7606 Old Muir Kirk Road
Town/Town Vicinity: Beltsville	County: Prince George's



Johnson-Crump House Site (PG: 62-015), 7606 Old Muirkirk Road Beltsville, Prince George's County, MD Laurel Quad, USGS Topographic Map, 1965, Revised 1979 Prepared by EHT Traceries, Inc., 2008

N



Johnson-Crump House Site (PG: 62-015), 7606 Old Muirkirk Road Beltsville, Prince George's County, MD Top – Façade (south elevation), looking north Photographed by EHT Traceries, Inc., 2008

P.G.-62-15
Johnson-Crump House
Beltsville Vicinity
Private

This substantial, three bay, two story log house reflects the improvements in log house construction made possible by land ownership and skilled labor. The principal block was built soon after 1887 by Notley Johnson, a black landowner. In 1907 another black family -- Major Anderson and his wife Sadie - purchased the farm, and over the years have remodelled it ot its present condition. Since its inception, all of the work on the house has been done by the resident families, the most energetic force being Mrs. Sadie Anderson Crump, who continues to live here with her second husband and who celebrated her centennial birthday in February, 1977. The changes to this house are in keeping with the evolution in housing among the black, landowning, middle class in rural Maryland in the decades of the turn of the century.

#### PRINCE GEORGE'S COUNTY

## HISTORIC SITE SUMMARY SHEET

Survey #:	P.G.	#62-15	Building Date	: 1887	
Building Na	ame:	Johnson-Crump Ho	use		
Location:	7606	Old Muirkirk Road	, Beltsville (Ross	ville), Md.	

Private/Vacant/Unimproved/Unexposed

### Description

The Johnson-Crump House, built in 1887 by Notley Johnson, was a two-story side-gabled log house. The hewn sill beams of the house rested on natural stone pilings, and there was a central brick chimney at the ridge. Early in the twentieth century, the original log structure was covered with horizontal board siding, and in the 1920's, a one-story kitchen wing was added, giving the building its L shape. A one-acre lot was sold out of Lot #11 in 1952, and on that lot stands the small side-gabled cottage which is the home of the present generation of the Crump family. The older Johnson-Crump house was demolished in 1981.

## Significance

The Johnson-Crump House was one of the first dwellings built in the 1886 subdivision of Rossville. It was constructed of log by Notley Johnson, on three-acre Lot #11 which he purchased in 1887; with its two-room plan and central chimney, it was representative of the modest dwellings built according to traditional methods by black farmers and laborers on newly acquired land. In 1913, Sadie Ross Anderson, daughter of Augustus Ross (who had built his house on Lot #1 of Rossville), purchased Lot #11, which Johnson had lost through default in mortgage. After this time, the windows of the log house were enlarged, and the log structure was covered with wood siding. After the death of Mrs. Anderson's husband, she married Israel Crump, and they raised their family in the old house. In 1952, Sadie and Israel Crump sold the westerly one acre of Lot #11 to their son, Oscar Crump, who erected on it the cottage in which he still resides. The original Johnson-Crump House was demolished in 1981.

Acreage: 2 acres

Survey No. PG#62-15

Maryland Historical Trust State Historic Sites Inventory Form Magi No.

DOE \_yes \_no

1. Nam	le (indicate pr	referred name)		
historic Joh	nson-Crump House	9		
and/or common				
2. Loca	ation			
street & number	7606 Old Muirl	cirk Road		not for publication
city, town Be	eltsville	Rossville vicinity of	congressional district	5
state MD		county	Prince George'	s .
3. Clas	sification			
Category  district building(s) structure site object	Ownership public private both Public Acquisition in process being considered not_applicable	Status  occupied unoccupied work in progress Accessible yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence religious scientific transportation X other:
4. Own	er of Prope	rty (give names a	nd mailing addresses	of <u>all</u> owners)
name Sad	ie A. Crump esta	te, c/o Oscar Crump		
street & number	760 <b>4</b> 01d Muirk	irk	telephone no	.:
city, town	Beltsville	state	and zip code MD	20705
5. Loca	ation of Leg	al Description	on	
courthouse, regi	stry of deeds, etc.	Prince George's C	County Courthouse	liber 1718
street & number	Main St	reet		folio 385
city, town	Upp	er Marlboro	state	MD
6. Rep	resentation	in Existing	Historical Surve	ys
title Prin	nce George's Cou	inty Inventory of	Historic Sites	
date 19	81		federal state	X countyloc
depository for su	urvey records Histo	ory Division, MNC	PPC	
city, town	Riverdale		state	MD

# 7. Description Survey No. PG#62-15

Condition excellent	deteriorated	Check one unaitered	Check one original site
good fair	x unexposed	aitered	moved date of move

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Johnson-Crump House, built in 1887 by Notley Johnson, was demolished within the last decade. It stood on Lot #11, one of the largest lots in the 1886 subdivision of Rossville.

This was a modest house, two stories high, with entrance in the center bay of the principal south facade. The house was built of log, and originally was lighted by small square windows. In this century the window openings were enlarged, and 2/2 double hung sashes were installed; weatherboard was applied over the log structure. The south entrance was sheltered by a facade-wide one-story shed-roof porch supported by plain posts.

The hewn sill beams of the house rested on natural stone pilings, and there was a central brick chimney at the ridge. In the 1920's, a rear kitchen wing was added, giving the building its L shape; this kitchen wing was one-story high with gable roof, had a tall brick chimney in the west plane of the roof, and was covered with board-and-batten siding.

The main block of the house consisted of two rooms on the first story, separated by a central entry hall which backed up on the central chimney. The west room was originally the kitchen, until the small kitchen wing was added, and the south room was the parlor. There was a second story bedroom over each of these spaces.

A one-acre lot was sold out of Lot #11 in 1952, and on that lot stands the small side-gabled cottage which is the home of the present generation of the Crump family. The older Johnson-Crump house was demolished in 1981.

X 1800-189 — 1900-	99 <u> </u>	chitecture t mmerce mmunications	en ex ind	ucation gineerin ploration dustry vention	g n/settlemer	mu	litary isic ilosophy litics/gover	social/ humanitarian theater transportation X other (specify) history
Specific dat	es 188	7	Builde	r/Archi	tect N	otley J	ohnson	
Ар	and/or plicable	Criteria:A  Exception:a ignificance:	E.F.	4	D D state	E _F	G	

Prepare both a summary paragraph of significance and a general statement of history and support.

The Johnson-Crump House was one of the first dwellings built in the 1886 subdivision of Rossville. It was constructed of log by Notley Johnson, on Lot #11 which he purchased in 1887; with its two-room plan and central chimney, it was representative of the modest dwellings built according to traditional methods by black farmers and laborers on newly acquired land.

In January 1868, William Minnix, a farmer of the Vanville District, sold a small piece of his farmland to six black men who had expressed the need of a "place of public worship." Accordingly, Henry Edwards, Thomas Queen, Thomas Matthews, Ferdinard Key, (K)notley Johnson and James Powell acquired 3/10 acre of land including a small graveyard already in use by the local black population, in trust for the erection of a "substantial building to be used as a place of worship and schoolhouse for the colored people." The log chapel which was built on this property came to be known as Queen's Chapel, in honor of one of these original trustees; it became the catalyst for the residential community which grew up immediately to the east twenty years later.

The land south and east of the Minnix farm was part of the estate of Mark Duvall. After Duvall's death in 1874, his real estate was divided among his heirs; in 1886 the Equity Court ordered the sale of some of this land. Part of Duvall's land adjoined Queen's Chapel on the east. A 24.8 acre parcel was surveyed by William H. Latimer, and divided into twelve unequal lots along the north side of the Muirkirk Road. Within a year, the twelve lots were purchased by the families of local blacks, most of whom were employed as laborers at the Muirkirk Iron Furnace. By late 1889, structures had been erected on all but one lot. Two of the new owner-residents, Thomas Matthews (lot #5) and (K)notley Johnson (lot #11) had been among the six founders of Queen's Chapel twenty years earlier. Another, Augustus Ross (lot #1), gave his name to the community. 3

MARYLAND HISTORICAL TRUST STATE HISTORIC SITES INVENTORY FORM Statement of Significance (continued) Survey No. PG#62-15
Section 8 Page 2

The focal point of the Rossville community was a large frame lodge building erected on the largest of the lots (#9) by the Benevolent Sons and Daughters of Abraham. An article (entitled "Rossville") in The Advertiser, published in Laurel, 2 October 1889, gives evidence that this lodge, known as Abraham Hall, was considered an impressive building from the beginning: "a portion of the old Duvall estate...has recently been subdivided and sold... to certain colored people residing in the vicinity of Muirkirk. The land is of excellent quality and the site very pleasant for residences. The Sons and Daughters of Abraham have purchased about five [sic] acres of land and have now about completed a very substantial two-story frame building, with ante-room and closets, to be used as a hall in which to hold the meetings of the society. New dwellings are now in course of erection, or have already been completed; for Mr. Ross, John Carter, Philip, Ezekiel and Thomas Williams, Carter Dickson, Notley Johnson, and Robert Taylor."4

Lot #11 was purchased by Notley Johnson and his wife, Hannah, late in 1887. According to Sadie Ross Crump, who later would buy Notley Johnson's property, farmer Johnson began in 1887 to fell trees on his property, squaring them into building logs, and raising the building with the help of other new lot owners. 6

In 1913, Sadie Ross Anderson, daughter of Augustus Ross (who had built his house on Lot #1 of Rossville), purchased Lot #11, which Johnson had lost through default in mortgage. It was after this time that the windows of the log house were enlarged, and the log structure was covered with wood siding. After the death of Mrs. Anderson's husband, she married Israel Crump, and they raised their family in the old house. In 1952, Sadie and Israel Crump sold the westerly one acre of Lot #11 to their son, Oscar Crump, who erected on it the cottage in which he still resides. 8

The Johnson-Crump house was one of the first houses built in Rossville; it was representative of the modest vernacular dwellings built at the end of the nineteenth century by black landowners. It was demolished in 1981.

#### Notes

- 1 Prince George's County Deed HB #1:130.
- Prince George's County Equity #1588; Prince George's County Deeds JWB #9:60, 203, 204, 205, 207, 208, 209, 210, 439, 603; JWB #10:131, 133.
- 3 Prince George's County Tax Assessments, 1888-89; The Advertiser, 2
  October 1889.

Survey No. PG#62-15
Section 8 Page 3

- 5 Prince George's County Deed JWB #10:133.
- 6 Interview with Sadie Ross Crump by George W. McDaniel, 1978.
- 7 Prince George's County Deed #79:487; see also P.G. Equity #2725.
- 8 Prince George's County Deed #1502:51.

<sup>4</sup> Ross built on Lot #1, Carter on Lot #6, the Williams families on Lots #3 and #8, Dickson (Dixon) on Lot #10, Johnson on Lot #11, and Taylor on Lot #12. cf. 1886 plat in Equity #1588.

## 9. Major Bibliographical References

Survey No. PG#62-15

See Notes, Item #8

10. Geographical Data	
Acreage of nominated property 2.0 acres  Quadrangle name Laurel, Section D  UTM References do NOT complete UTM references	Tax map 13, parcel 104  Quadrangle scale 1:24000
Zone Easting Northing	Zone Easting Northing
C	P
Verbal boundary description and justification  . List all states and counties for properties overlapping	state or county boundaries
state code co	unty code
state code co	unty code
11. Form Prepared By	
name/title Susan G. Pearl, Research/Architect	ural Historian and G. W. McDaniel
organization P.G. C. Historic Preservation Co	mm'n date March 1989 (1978)
street & number c/o M-NCPPC, 14741 Gov.Oden Bow	ie Drive <sub>telephone</sub> (301) 952-3521
city or town Upper Marlboro	state Maryland

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House

21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

P. G: 62-15 Johnson-Crump House Muirkirk Private

This handsome two story log house was built by a black landowner, Notley Johnson. It contains two rooms downstairs and two upstairs. In 1907, it was purchased by Sadie Crump, who improved the exterior and interior, enlarged the house and gave it the appearance of a fine, modestly appointed dwelling. The house is evidence of the evolution in housing among the rural black middle class in the decades of the turn of the century.

GEORGE W. McDANIEL 635 G ST. S.E. WASHINGTON, DC 20003

## Maryland Historical Trust State Historic Sites Inventory Form

Magi No.

DOE \_\_yes \_\_no

1. Nam	e (indicate pr	referred name)		
historic John	son-Crump House	9		
and/or common				
2. Loca	tion			
street & number	7606 Old Muirl	kirk Road		_ not for publication
city, town Bel	ltsville	Rossvillevicinity of	congressional district	5
state MD		county	Prince George's	S
	sification			
Category  district building(s) structure site object	Ownership  public private both Public Acquisition in process being considered not_applicable	Status  occupied unoccupied work in progress Accessible yes: restricted yes: unrestricted no	Present Use agriculture commercial educational entertainment government industrial military	museum park private residence religious scientific transportation other:
4. Own	er of Prope	rty (give names an	nd mailing addresses	of <u>all</u> owners)
name Sadi	e A. Crump			
street & number	7606 Old Muirl	cirk	telephone no	.:
city, town B	eltsville	state	and zip code MD	20705
5. Loca	tion of Leg	al Description	on	
courthouse, regis	try of deeds, etc.	Prince George's C	ounty Courthouse	liber 1718
street & number	Main St	reet		folio 385
city, town		oer Marlboro	state	MD
	esentation	in Existing	Historical Surve	eys
title Prin	ce George's Cou	inty Inventory of	Historic Sites	
date 197			federal state	X countyloca
epository for sur	vey records Histo	ory Division, MNC		_
city, town	Riverdale		state	MD

7	Description	
	Description	

Survey No. PG#62-15

Condition		Check one	Check one			
excellent	deteriorated	unaltered	original s	site		
good	ruins	altered	moved	date of	move	_
fair	_X unexposed					

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

The Johnson-Crump House was a plain two-story frame gable-roofed vernacular dwelling, one of the first houses built in Rossville.

8. S	ignificance	Survey No. PG#62-15
1600	aistoric archeology-prehistoric	Check and justify below  c
Specific	dates	Builder/Architect
check:	and/or	A _B _C _D  A _B _C _D _E _F _G  national state local

8. Significance

support.

This dwelling was one of the first houses built in Rossville, a small black community (largely of laborers at the Muirkirk Furnace) which was formed in the 1880's. Notley Johnson built this house circa 1888, on lot #11, one of the larger lots in the

Prepare both a summary paragraph of significance and a general statement of history and

subdivision of Rossville. In 1913, the house and lot were sold to Sadie Anderson, daughter of Augustus Ross (for whom Rossville was named). It has remained in her family, the Crump family, to the present day.

The house was in deteriorating condition when it was surveyed in 1978, and was destroyed shortly afterwards.

10. Geographical Data	
Acreage of nominated property 2.0 acres  Quadrangle name Laurel, Section D  UTM References do NOT complete UTM references	Tax Map 13,parcel 104  Quadrangle scale
Zone Easting Northing	Zone Easting Northing
C	D
Verbal boundary description and justification  List all states and counties for properties overlapping	state or county boundaries
state code code	unty code
state code code	unty code
11. Form Prepared By	
name/title Susan G. Pearl, Research Hist	orian
organization Historic Preservation Commis	sion date
street & number c/o County Planning, MNCPPC	telephone 952-3521
Upper Marlboro,	state MD 20772

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust

Shaw House

21 State Circle

Annapolis, Maryland 21401

(301) 269-2438

MARYLAND HISTORICAL TRUST MAGE # 1705435604

## INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME						
HISTORIC	The	Johnson-Crum	р Нои	ıse		
AND/OR COM	MON					
2 LOCAT	rion					
STREET & NU	MBER	7606 Old Mui	rkirk	Road		
CITY, TOWN		Beltsville	x	VICINITY OF	CONGRESSIONAL DIS	STRICT
STATE		Maryland			COUNTY	e George's
3 CLASS	IFIC					
CATEG DISTRICT	ORY	OWNERSHIP _PUBLIC		STATUS X_OCCUPIED	PRE AGRICULTURE	ESENT USEMUSEUM
BUILDING  &_STRUCTU SITE		X_PRIVATE _BOTH PUBLIC ACQUIS	ITION	UNOCCUPIEDWORK IN PROGRESS ACCESSIBLE	COMMERCIAL EDUCATIONAL ENTERTAINMEN	PARK  X_PRIVATE RESIDENCE  NTRELIGIOUS
OBJECT		_IN PROCESSBEING CONSIDERED		X_YES: RESTRICTED YES: UNRESTRICTED NO	GOVERNMENT INDUSTRIAL MILITARY	SCIENTIFICTRANSPORTATIONOTHER
4 OWNE	R OF	PROPERTY				
NAME		Sadie Crump				
STREET & NU	MBER			•	Telephone #: 1	None
7	606 (	Old Mirkirk Ro	oad			
CITY, TOWN	elts	ville	x	VICINITY OF	Maryland	zip code 20705
5 LOCAT	rion	OF LEGAL DE	ESCR	IPTION	Liber #: JB 79	9
COURTHOUSI REGISTRY OF	E. DEEDS, E	ac Prince Geor	ge's	County Courth	Folio #: 489 nouse, Registry	
STREET & NU	MBER		25			
CITY, TOWN		Upper Marlbo			STATE	
e DEDDE	CEN			NC CLIDVEVE	Marylar	nd
(PANTED AT	SEN	TATION IN E2	71911	ING SURVEYS		
TITLE	No	one				
DATE				FEDERAL	_STATE _COUNTY _LOC	AL
DEPOSITORY SURVEY RECO			_			
CITY, TOWN	-				STATE	

\_FAIR

CONDITION

\_EXCELLENT \_\_DETERIORATED X\_GOOD

RUINS UNEXPOSED CHECK ONE

\_UNALTERED XALTERED

**CHECK ONE** 

XORIGINAL SITE \_MOVED

## DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

This attractive house stands about 50 yards from Old Muirkirk Road on the gentle slope of the hillside descending east from the road. In front of it is a well-kept lawn, with flowers bordering both the lawn and the house. On either side of the front length stand two large plaster pots for flowers, made by the owner, Mrs. Sadie Crump. She had her centennial birthday in February 1977.

The house faces west towards the road. Today it is weatherboarded and painted yellow with white trims giving it the appearance of a middle class landowner's frame house. But when it was built in the late 19th century as the home of its owner and occupant, Notley Johnson, it was a plain log house with no sheathing and was not whitewashed. Unlike most log houses of black families of the 19th century, this one was built with two stories. The facade had the typical three-bay arrangement, with two windows flanking a centrally located door with matching windows above those below. When built, the windows were much smaller and square in shape, similar to windows in other log houses of black families, according to Mrs. Crump. After she purchased the property, Mrs. Crump enlarged the windows and installed the double-hung sashes with two over two lights. The northern gable end has no window opening, like the house nearby of her father, Augustus Ross, which has also been recorded as part of this survey. The souther gable end did have one window in the upstairs. Probably the window was omitted from the northern gable end to keep out the cold winds, while the southern gable did have a window for the sunlight from the southern exposure. The windows in the facade provided the illumination for the downstairs room in the northern gable end. Thus, the arrangement is practical.

The foundations of the house (hewn sills) rested on stone pil ing on three sides, but directly on the ground underneath the facade. No rot or termite infestation has resulted so far, perhaps because of Mrs. Crump's traditional pesticide: lime that she dowses the underparts of the house with periodically.

The floor plan of the interior of the original block consists of two rooms downstairs, two upstairs. The front door opens directly into. a short foyer between the two rooms with the back wall being the frame around the central chimney. The north room was originally the kitchen, the cooking being done over a wood stove piped into the central chimney. In the northeast corner, a dog-leg stairway ascended the two walls. Originally, the treads were unenclosed, but Mrs. Crump has boxed them in with narrow, plain planks during her improvements of the log house. In the east wall (rear), a door opened originally to the outside, but Mrs. Crump has added a board and batten, frame kitchen with a shed room attached to it about fifty years ago.

## 8 SIGNIFICANCE

ERIOD	AF	REAS OF SIGNIFICANCE CH	IECK AND JUSTIFY BELOW	
PREHISTORIC	ARCHEOLOGY-PREHISTORIC	COMMUNITY PLANNING	_LANDSCAPE ARCHITECTURE	RELIGION
_1400-1499	_ARCHEOLOGY-HISTORIC	CONSERVATION	_LAW	SCIENCE
_1500-1599	AGRICULTURE	ECONOMICS	LITERATURE	SCULPTURE
_1600-1699	X_ARCHITECTURE	EDUCATION	MILITARY	*SOCIAL/HUMANITARIAN
_1700-1799	ART	ENGINEERING	MUSIC	_THEATER
X_1800-1899	COMMERCE	_EXPLORATION/SETTLEMENT	PHILOSOPHY	_TRANSPORTATION
_1900-	COMMUNICATIONS	_INDUSTRY	POLITICS/GOVERNMENT	*OTHER (SPECIFY)
		_INVENTION	Black	History

SPECIFIC DATES

Circa 1887

BUILDER/ARCHITECT

Notley Johnson

#### STATEMENT OF SIGNIFICANCE

This house is valuable evidence of the evolution of the houses of the emerging black middle class in the late 19th century. According to Mrs. Crump, she and her first husband bought the house from Notley Johnson, who had built it. Deed records show that he had purchased the land in 1887, with his wife, Hannah, as co-signer. According to Mrs. Crump, who was born in 1877 and who remembers the construction of this house when she was ten about ten years old, Johnson felled the trees on his land, hewn them into squared logs, and raised this house in the community helping him to put on the roof. Since Johnson owned the land, he could use his wood as he saw fit and build a larger house than commonly found among landless blacks. According to Mrs. Crump, Johnson built a log house instead of a frame one because he was accustomed to building and living in them, her memory of him remembering him as being of the "old style."

In 1907, Mrs. Crump and her first husband, Major Anderson, bought this property. After his death, she married her present husband, of the property of the family -- which includes four generations. Very strong support comes from their son, Oscar Crump, who with his wife, lives next door to them in a pleasant, one and a half-story house built in the 1950's, a slide of which is included in this survey. About 200 yards north of this house stands the house of Mrs. Crump's father, Augustus Ross. Thus, along this road stand the houses of an extended family that has remained closely knit throughout the 20th century. Though the land is no longer farmed, it is well-maintained, and is still cultivated in vegetable gardens. Several of the old fruit trees planted by the founders of the community still remain.

## 9 MAJOR BIBLIOGRAPHICAL REFERENCES

CONTINUE ON SEPARAT	TE SHEET IF NE	ECESSARY		
10 GEOGRAPHICAL D	ATA			
ACREAGE OF NOMINATED PROPERT				
		-		
VERBAL BOUNDARY DESCRIP	PTION			
VEHOLE BOOKBAIL BEGGIN			see a see T	
ed eses			iner, w	
39				
LIST ALL STATES AND C	OUNTIES FOR PROPE	RTIES OVERLAPPING	STATE OR COUNTY BOUNDARI	ES
STATE		COUNTY		
		COUNTY		4
STATE		COUNTY		
11 FORM PREPARED I	3Y			
NAME / TITLE				
George W. McDar	niel			
ORGANIZATION	0.0	20 86	DATE	
Maryland Commis	ssion on Afro-	-American His	tory and Culture	
STREET & NUMBER			TELEPHONE	

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.

The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust

20 Dean Street

Annapolis, Maryland

CITY OR TOWN

The Shaw House, 21 State Circle

Annapolis, Maryland 21401

(301) 267-1438

The Johnson-Crump House Prince George's County Maryland

(DESCRIPTION CONTINUED)

Item No. 7

Page 1


The south room was the "sitting room." Its fireplace has now been filled in. On the walls hang early 20th century paintings and prints, family photographs, and religious paintings of the Virgin Mary and Jesus which, though dusty from neglect since this elderly couple no longer entertain, reveal the personal possessions and values of this family in the early 20th century.


In addition to the "improvements" already mentioned, Mrs. Crump lathed and plastered the interior walls of the log house herself, and installed picture moldings along the walls. The result is that the humble log dwelling was converted in appearance to that of a fine-frame house.


atlanta - 43 th


1114 5 Not 50

himselve by algorith











JOHNSON- CRUMP HOUSE P.G., WEST VIEW, Facade BELTSVILLE, MD. GWM



JOHNSON - CRUMP HOUSE

P.G. 
NORTH VIEW

Be 1+5 ville, md. Gum 6/11



P6:62-15

Crump family: L-R: Oscar (Rump, Sadie Crump, Israel Crump Daughter of S. + I. CRIMP. I steal coump, hipe ) Oscar. P.G. Muir Kirk, Et. Vic. Baltsvilla, md. Gum

90/16



Johnson-Crump House South Gable End Beltsville, md. & Sum 6/77



P6:62-15 CRump family L-R Oscar Coump, Jadie Crump, Israel. GRump, + wite of oscar CRump. Beltswille, md.

10/76